



Republic of the Philippines
MSU-ILIGAN INSTITUTE OF TECHNOLOGY

Office of the Bids and Awards Committee

Office of the BAC Secretariat, 3rd Flr, MSU-IIT Canteen Annex, Tibanga, Iligan City
Telefax No. (063) 225-4926

INVITATION TO BID

- A. The MSU- Iligan Institute of Technology through its Bids and Awards Committee invites interested suppliers to apply for eligibility and to bid for the hereunder project:

Name of Project :
Location :
Approved Budget :
Source of Fund :
Delivery Period :
Non-refundable Bidder Fee :
Reference No. : -

-

Supply of labor and materials in the renovation of comfort room at Rooms 117 (1st floor) and Room 228, CSM Annex Building.

SCOPE OF WORKS:

1. Removal of old pantry and existing tiles.
2. Installation of 200mm x 200mm floor tiles (beige) and 200mm x 300mm wall tiles. Color to be determined by end-user.
3. Installation of 3.5mm hardilite board on light metal frames with off white paints.
4. Installation of plumbing pipes, fittings and fixtures with complete accessories: includes installation of toilet paper holder and soap holder.
At Room 228 – install lavatory on pedestal basin with faucet and two (2) units Water closet
At Room 117 – install wall hung lavatory with faucet and two (2) units water closet
5. Installation of electrical wirings and fixtures with complete accessories.
6. Includes painting of walls and other areas affected.
7. Includes installation of 6mm thick bronze glass awning windows on 50mm x 100mm tubular analoc frames.
8. Installation of PVC bathroom door with jambs and vent with locks and keys.
(please see attached sketch plan)

TERMS AND CONDITIONS:

1. Actual site inspection is highly recommended to get actual measurements and totality of work.
2. Secure site inspection certificate from PPD.
3. Contractor to

4. Installation of 6mm thick clear glass single swing door with 6mm thick clear glass partition on 50mm x 100mm tubular analoc frames. (1.55m x 1.80m – 1 set)
5. Installation of 6mm thick clear glass partition on 50mm x 100mm tubular analoc frames. (2.79m x 1.80m - 1 set)
6. Cleaning of areas after installation. (please see attached sketch plan)

TERMS AND CONDITIONS:

7. Actual site inspection is highly recommended to get actual measurements and totality of work.
8. Secure site inspection certificate from PPD.
9. Contractor to supply labor and materials and should have appropriate tools, equipment, technical know-how, supervision necessary to complete the project.
10. Submit quotation to include:
 - Detailed bill of materials & total cost.
 - Detailed labor cost & no. of days to complete
11. Coordinate with PPD before the start of the project.
12. Have filed Accreditation from MSU-IIT Procurement office.

ABC for Lot 2PhP75,766.90

- B. Secure Checklist of bidding documents from the BAC Secretariat Office after payment of the non-refundable bidder's fee. Accomplish the duly certified requirements in three (3) copies, fl