



-

Supply of Labor and Materials in the installation / demolition / renovation of the following Scope of Works at College of Business Administration and Accountancy Comfort Rooms.

SCOPE OF WORKS:

1. Demolition of all affected portion of the said renovation e.g. partition, ceiling etc. Please refer to the attached sketch plan.
2. Masonry Works: Construction of new concrete partition and counter of the said renovation. Please see attached sketch plan.
3. Tile Works: Installation of tiles of the following room:
  - Female Comfort Room – Installation of unglazed ceramic floor tiles 8" x 8" (Basalto Brown), Installation of glazed ceramic wall tiles 8" x 12" (Light beige), Installation of counter top granite tile 16" x 16" (Black Galaxy granite Premium).
  - Male Comfort Room – Installation of unglazed ceramic floor tiles 8" x 8" (Dark Grey), Installation of glazed ceramic wall tiles 8" x 12" (Light Grey), Installation of counter top granite tile 16" x 16" (Black Galaxy Granite Premium).
  - Common Male / Female Comfort Room – Installation of unglazed ceramic floor tiles 8" x 8" (Black), Installation of glazed ceramic wall tiles 8" x 12" (Sampaguita lavender), Installation of counter top granite tile 16" x 16" (Black Galaxy Granite Premium).

\*Please see attached sketch plan for reference\*
4. Plumbing Works:  
Re

3. Fabrication and installation of three (3) units hanging cabinets.  
(please see attached sketch plan)

TERMS AND CONDITIONS:

1. Actual site inspection is highly recommended to get actual measurements and totality of work.
2. Secure site inspection certificate from PPD.
3. Contractor to supply labor and materials and should have appropriate tools, equipment, technical know-how, supervision necessary to complete the project.
4. Submit quotation to include:
  - Detailed bill of materials & total cost.
  - Detailed labor cost & no. of days to complete
5. Coordinate with PPD before the start of the project.
6. Have filed Accreditation from MSU-IIT Procurement office.

BC for Lot 3 .....PhP127,400.00

-

Supply of labor and materials for the Renovation of Stockroom for the Society Office at the Chemistry Department., 3<sup>rd</sup> floor, CSM Bldg.

SCOPE OF WORKS:

1. Removal of existing floor tiles.
2. Removal of existing wall tiles.
3. Removal of existing divider.
4. Cover existing manhole at ceiling.
5. Painting works: a.) ceiling b.) concrete walling
6. Removal of existing windows.
7. Installation of 6mm thick bronze glass windows on 45mm x 100mm tubular aluminum frames (analoc finish). 2 sets - 0.90m x 1.465m
8. Installation of 6mm thick bronze glass swing door on 45mm x 100mm tubular aluminum frame (analoc finish). 1 set - 0.969m x 2.10m
9. Clearing of areas before demobilization.  
(please see attached sketch)

TERMS AND CONDITIONk1Me246(tt)-3(a)-3(c)10(h)-3(e)6(d)-3( ske)-5(tc)8(h) Tm((pl2sh)-3().)JTETBT1 0 0 i9(((pl2

TERMS AND CONDITIONS:

1. Actual site inspection is highly recommended to get actual measurements and totality of work.
2. Secure site inspection certificate from PPD.
3. Contractor to supply labor and materials and should have appropriate tools, equipment, technical know-how, supervision necessary to complete the project.
- 4.