



		<p>1 unit CW-5142 Full Fabric Panel Partition ( 5in. high)  4 units CW-5124 Full Fabric Panel Partition ( 51 in. High)</p> <p>:</p> <p>2 units 3W-51 3-Way Connector  4 units EC-51 End Cap</p> <p>2 units WS-2442 worksurface (faculty)  1 unit FST-2436 Table for server  5 units CWS-2(2454) Computer Workstation 2-Station  5 units CWS-3(2481) computer Workstation 3-station</p> <p>With Free Installation</p>
--	--	--

Supply of labor and materials in the Renovation of Room 126, CSM Building.

#### SCOPE OF WORKS:

1. Removal of existing 2" x 3" wood, existing false beam, door and windows.
2. Installation of 3.5mm thick hardilite board on light metal frames with white paint ceiling.
3. Installation of 3.5mm thick hardilite board on light metal frames with white paint false beams.
4. Installation of 6mm thick bronze glass door on 4.5mm x 100mm tubular analoc frames with lock and keys and its accessories.  
D -1 2 sets 0.97m x 2.12m
5. Installation of 6mm thick bronze glass fixed transom/sliding glass windows on 45mm x 100mm tubular analoc frames.  
W - 1 1 set 4.08m x 1.47m  
W - 2 1 set 4.05m x 1.47m
6. Installation of fabricated sliding blackboard.
7. Replacement of 10cm x 10cm tiles into 30cm x 30cm white tiles.
8. Installation of 110mm x 220mm x 270mm projector frames.
9. Installation of electrical fixtures, wirings and complete accessories.
10. Installation of 4" CHB smooth finishing and painting works.
11. Repainting of existing folding partition, beam, columns, floor slab and existing walls. Refer To PPD for the color.
12. Painting of 1" dia. G.I. Pipe with white paint
13. Clearing of areas before demobilization.

#### TERMS AND CONDITIONS:

1. Actual site inspection is highly recommended to get actual measurements and totality of work.
2. Secure site inspection certificate from PPD.
3. Contractor to supply labor and materials and should have appropriate tools, equipment, technical know-how, supervision necessary to complete the project.
4. Submit quotation to include:  
-Cost per scope of works  
-Number of days to complete
5. Coordinate with PPD before the start of the project.
6. Have filed Accreditation from MSU-IIT Procurement office.

