



4. Removal of existing water and waste pipes, water closet, and doors.
5. Installation of new water and waste pipelines.
6. Installation of water closet, lavatory and other fixtures with complete accessories.
7. Installation of floor and wall tiles.
8. Installation of wall flushed mirrors and hanging shelves.
9. Installation of marine flush doors and 6mm thick bronze glass awning windows on 45mm x

